

WALNUT CREEK INTERMEDIATE SCHOOL PROJECT

ADDENDUM #1

- 1. REFERENCE SHEET A2.01 & A2.02 – GENERAL NOTE #2 (A2.01) & #3 (A2.02) – WHICH STATES WHICH ROOMS WE ARE TO REMOVE SHEETROCK/PLYWOOD FROM EXISTING WALLS AND WHICH ROOMS WE ARE TO ONLY DO SELECTIVE DEMOLITION OF WALL FINISHES FOR NEW WORK.**

PLEASE FOLLOW GENERAL NOTE #9 – WHICH STATES CONTRACTOR OPTION TO REMOVE ALL FINISHES AND REPLACE IN KIND.

SO FOR BUILDING #100 – FOR ROOM 101, 102, 103, 104, 107A, 108 – REMOVE ALL WALL FINISHES WHICH MEANS ALL WALL FINISHES ON EXISTING WALLS WITHING BUILDING 100 ARE TO BE REMOVED DOWN TO STUDS AND REPLACED WITH NEW 5/8” GYP BOARD PER SECTION 09 29 00 TO LEVEL 5 WITH ALL NEW INSULATION

FOR BUILDING #150 – REMOVE ALL INTERIOR WALL FINISHES ON EXISTING WALLS DOWN TO STUDS AND REPLACED WITH NEW 5/8” GYP BOARD PER SECTION 09 29 00 TO LEVEL 5 WITH ALL NEW INSULATION

FOR BUILDING #200 – FOR ROOM 201, 202, 203, 204, 207, 208, 209 – REMOVE ALL WALL FINISHES WHICH MEANS ALL WALL FINISHES ON EXISTING WALLS WITHING BUILDING 200 ARE TO BE REMOVED DOWN TO STUDS AND REPLACED WITH NEW 5/8” GYP BOARD PER SECTION 09 29 00 TO LEVEL 5 WITH ALL NEW INSULATION